CEQA # 10564

State of California – The Resources Agency
DEPARTMENT OF PARKS AND RECREATION

NOTICE OF EXEMPTION

TO: Office of Planning and Research
1400 Tenth Street
Sacramento, CA 95814
FAX (916) 323-3018

FROM: Department of Parks and Recreation
Northern Service Center
One Capitol Mall, Suite 410
Sacramento, CA 95814

PROJECT TITLE: Sewage System Improvements

LOCATION: Angel Island State Park **COUNTY:** Marin

DESCRIPTION OF THE NATURE AND PURPOSE OF PROJECT: Improve the failing sewage disposal system on Angel Island State Park to meet current health and safety requirements. Work will:

At seven lift stations and water treatment building

- Install new control system and communication components in or on existing buildings.
- Replace control panels, as needed.
- Replace access lids.
- Repair or replace plumbing within existing lift station vaults, as needed.
- Excavate approximately 30" deep by 18" wide to move pull boxes at each location.

At Lift Station 1

- Excavate approximately 5' x 5' hole approximately 3' deep to install valve and install 3" shutoff valve on force main.
- Install antenna (radio) on new control panel.

At Lift Station 2, 3 5, 7 and the water treatment building

- Install radio antenna on existing buildings or control panel boxes.

Fire House

- Excavate a trench approximately 30" by 18" by 110' and install approximately 110' of gravity sewer line from the firehouse to the sewer main in the road.
- Install cleanout on new gravity sewer line.
- Abandon the existing septic pipe and tank and fill both with concrete slurry.
- Install new radio antenna on maintenance building.

Staff Housing at East Garrison

- Excavate a trench 30" by 18" wide by 400' long and replace approximately 400' of sagging gravity pipe. Placement of pipe will be in existing roadway.
- Excavate two trenches, one 30" deep by 18" wide by 80' long from chapel to sewer main line and one 35' long trench from the administration building to the sewer main line then install new lateral sewer pipes.
- Replace two cleanouts at the chapel and administration building.

At Lift Station 6

- Excavate several inches around the existing fiberglass basin and build a concrete riser to protect the basin.
- Install new radio antenna on control panel.

Subsurface drip disposal system

- Excavate approximately 16' long by 30" wide and up to 8" to extend concrete pad.
- Install structure over the 8' wide by 16' long concrete pad that houses the control panel, filter, and headworks.

PUBLIC AGENCY APPROVING THE PROJECT: California Department of Parks and Recreation

NAME OF DIVISION OR DISTRICT CARRYING OUT THE PROJECT: Acquisition and Development

EXEMPT STATUS: ☒ Categorical Exemption Classes: 1, 2, 3, 4, 11
Sections: 15301, 15302, 15303, 15304, 15311

REASONS WHY PROJECT IS EXEMPT: Project consists of the minor alteration of existing public structures and facilities involving negligible expansion of use beyond current levels the construction and location of limited numbers of new small facilities, the minor alteration in the condition of land and vegetation that does not involve removal of healthy, mature, scenic trees and the construction of minor structures accessory to existing institutional facilities included in the Department of Parks and Recreation's list of exempt activities in accordance with CCR § 15300.4.

CONTACT: Patti Dumont
Northern Service Center

PHONE NO.: (916) 445-8779
EMAIL: Patti.Dumont@parks.ca.gov

4-23-14

Kathleen Amann
Deputy Director
Acquisition and Development

Date

RECEIVED
APR 24 2014
STATE CLEARING HOUSE