



State of California – Natural Resources Agency
DEPARTMENT OF PARKS AND RECREATION

NOTICE OF EXEMPTION

TO: Office of Planning and Research
1400 Tenth Street
Sacramento, CA 95814

FROM: Department of Parks and Recreation
One Capitol Mall, Suite 410
Sacramento, CA 95814

PROJECT TITLE: Millerton North Shore Accessibility Improvements

LOCATION: Millerton State Recreation Area **COUNTY:** Madera

DESCRIPTION OF THE NATURE AND PURPOSE OF PROJECT: Upgrade various facilities at the Meadows, Fort Miller, and Rocky Point Campgrounds and the North Shore Equestrian Camp and Campfire Center areas at Millerton SRA, to meet accessibility standards. Work will:

At Campsites #120, 132, 133, and 144 in the Meadows RV Campground:

- Remove existing water stations, excavate to level a total area of approximately 100ft² x up to 8" in depth, form and pour 60"x60"x4" concrete pad at each site, and reinstall water stations with compliant drains and catch basins;
- Remove existing electrical hookups and excavate a total area of approximately 100ft² x up to 8" in depth, form and pour 60"x60"x4" compliant concrete pad at each site and reinstall electrical box;
- Remove existing fire rings as necessary, excavate to level a total area of approximately 100ft² x up to 8" in depth, form, pour and install 11'x11' raised tactile paving (detectable warning surfaces) and reinstall fire rings.

At Campsite # 43 in the Fort Miller Campground:

- Excavate an approximately 100ft² area up to 8" in depth to level, form and pour a 5'x20'x6" concrete accessible walkway from the parking space to the table pad;
- Remove existing water station excavate to level a total area of approximately 25ft² x up to 8" in depth, form and pour 60"x60"x4" concrete pad at each site, and reinstall water stations with compliant drain and catch basin;
- Remove existing fire ring, excavate to level a total area of approximately 100ft² x up to 8" in depth, form, pour and install 11'x11' raised tactile paving (detectable warning surfaces) and reinstall fire ring.

At the Rocky Point Campground Combo Building:

- Excavate approximately 75ft² area up to 8" in depth, form and pour 2, 5'x15'x6" concrete accessible walkways from the campground road to the Combo building, remove and replace drinking fountain, remove tiled bench in shower room and install signs;

At Rocky Point Campground Campsite #3:

- Excavate to level a total area of approximately 110ft² x up to 8" in depth, form and pour 48"x216"x6" concrete apron adjacent to the existing parking pad;
- Remove existing water station excavate to level a total area of approximately 25ft² x up to 8" in depth, form and pour 60"x60"x4" concrete pad at each site, and reinstall water stations with compliant drain and catch basin;
- Remove existing fire ring, excavate to level a total area of approximately 100ft² x up to 8" in depth, form, pour and install 11'x11' raised tactile paving (detectable warning surfaces) and reinstall fire ring.

At Rocky Point Campground Campsite #5:

- Remove all existing improvements including railroad ties, asphalt, and concrete pad, and re-level the entire site, excavate an approximately 196ft² area up to 8" in depth, form and pour a 14'x14'x6" concrete picnic table pad;
- Excavate an approximately 400ft² area up to 8" in depth, form and pour a 20'x20'x6" concrete parking area;
- Remove existing water station excavate to level a total area of approximately 25ft² x up to 8" in depth, form and pour 60"x60"x4" concrete pad at each site, and reinstall water stations with compliant drain and catch basin;

- Remove existing fire ring, excavate to level a total area of approximately 100ft² x up to 8" in depth, form, pour and install 11'x11' raised tactile paving (detectable warning surfaces) and reinstall fire ring.
- Excavate four holes, 24 inches in diameter by 36 inches deep and install shade ramada.

At Rocky Point Campground Campsite # 16:

- Remove existing uneven asphalt, form and pour concrete a 18'x20'x6" concrete area adjacent to the existing table pad;
- Remove and relocate existing food locker;
- Remove existing water station excavate to level a total area of approximately 25ft² x up to 8" in depth, form and pour 60"x60"x4" concrete pad at each site, and reinstall water stations with compliant drain and catch basin;
- Remove existing fire ring, excavate to level a total area of approximately 100ft² x up to 8" in depth, form, pour and install 11'x11' raised tactile paving (detectable warning surfaces) and reinstall fire ring.

At the North Shore Equestrian Camp:

- Perform minor leveling as necessary within the camp as/where necessary.
- Excavate four holes, 24 inches in diameter by 36 inches deep and install shade ramada;
- Remove all existing improvements including railroad ties, asphalt, and concrete pad, and re-level the entire site, excavate an approximately 240ft² area up to 8" in depth, form and pour a 6'x40'x6" concrete picnic table pad;
- Replace existing chemical toilet with an ADA compliant model;
- Construct an equestrian wooden access ramp and mounting platform.

At the Campfire Center:

- Remove and reconstruct the existing speaker's podium would be rebuilt and benches and fire ring shortened.
- Excavate an approximately ___ft² area up to 8" in depth to level, form and pour a ___'x___'x6" concrete accessible walkway connecting the north side bench and the speaker's podium;
- Excavate an approximately 100ft² area up to 8" in depth to level, form and pour a 5'x20'x6" concrete accessible walkway parallel to the front row of benches;
- Excavate an approximately 20ft² area up to 8" in depth to level, form and pour a 4'x4'x6" concrete pad and install a "companion seating" bench;
- Excavate up to two post holes 8" diameter x 24" in depth to install necessary signage.

PUBLIC AGENCY APPROVING THE PROJECT: California Department of Parks and Recreation

NAME OF DIVISION OR DISTRICT CARRYING OUT THE PROJECT: Accessibility Section

EXEMPT STATUS:

Categorical Exemption *Class: 1, 2, 3, & 4 Section: 15301, 15302, 15303, & 15304*

REASONS WHY PROJECT IS EXEMPT: Project consists of the minor alteration of existing public facilities and topographic features involving negligible expansion of use beyond current levels; replacement of existing structures/facilities where the new structure will be located on the same site as the structure replaced and will have substantially the same purpose and capacity; construction of new small facilities or structures and the installation of small new equipment and facilities in small structures, minor public alterations in the condition of land and vegetation which do not involve removal of healthy, mature, scenic trees; included as "modifications of existing facilities for accessibility", in the Department of Parks and Recreation's list of exempt activities, in accordance with CCR 15300.4.


CONTACT: Brad Michalk
Northern Service Center

PHONE NO.: (916) 445-8783
EMAIL: brad.michalk@parks.ca.gov

Governor's Office of Planning & Research

FEB 09 2016

STATE CLEARINGHOUSE



Brian Dewey, Assistant Deputy Director
Northern Service Center

2-3-2016

DATE