



NOTICE OF EXEMPTION

TO: Office of Planning and Research
1400 Tenth Street
Sacramento, CA 95814

FROM: Department of Parks and Recreation
1416 Ninth Street
P.O. Box 942896
Sacramento, CA 94296-0001

PROJECT TITLE: Burney Creek Trail Accessibility Improvements

LOCATION: McArthur-Burney Falls Memorial State Park

COUNTY: Shasta

DESCRIPTION OF THE NATURE AND PURPOSE OF PROJECT: This project retrofits approximately one linear mile of Burney Creek Trail at McArthur-Burney Falls Memorial State Park to meet accessibility requirements as described in the "California State Parks Accessibility Guidelines." The project includes the following work:

- **Trail:** Use up to 2 feet of fill to re-grade an approximately 6,000 square foot area adjacent to two campsites to correct soil erosion onto Burney Creek Trail. Level approximately 611 linear feet of unpaved trail by filling and grading the trail surface. Remove asphalt from approximately 1,190 linear feet of trail and replace with a compacted aggregate and soil mix up to 8 inches in depth. Re-align four trail segments that total about 1,058 feet so that grade throughout the length of the Burney Creek Trail is accessible. Replace hand rail along approximately 143 feet of trail by installing a wooden post sill and securing the sill with rebar poles driven into the ground up to 4 feet in depth. Cover the sill with up to 2 feet of fill to weigh down the sill and be used as the trail tread. Install approximately 784 linear feet of 3-foot high rock retaining wall with soil fill on the upslope side of the wall to reconstruct the trail in several locations. Remove an approximately 50 foot long asphalt trail spur between Burney Creek Trail and Burney Falls pool and approximately 2,904 feet of abandoned trail segments/parallel trails. Rehabilitate to a natural condition by de-compacting and re-contouring the soil along the trail alignments and covering the area with vegetative duff.
- **Fishing Pier:** Construct a new accessible fishing pier up to 225 square feet in size on the shore of Lake Britton and a 200 foot long trail spur from Burney Creek Trail to the fishing pier.
- **Pullouts:** Improve two existing pullouts and install four new pullouts along the trail. Install one bench at each pullout. Five pullouts will measure approximately 25 square feet and one just upstream from Burney Falls will measure about 80 square feet.
- **Signage:** Install three new accessible trail signs and replace four non-accessible interpretive panels with accessible panels.

DPR-approved standard project requirements have been incorporated into the Burney Creek Accessibility Improvements Project. A list of project-specific project requirements can be viewed by contacting the environmental coordinator listed below.

PUBLIC AGENCY APPROVING THE PROJECT: California Department of Parks and Recreation

NAME OF DIVISION OR DISTRICT CARRYING OUT THE PROJECT: Acquisition and Development


EXEMPT STATUS:

☒ Categorical Exemption *Classes:* 1, 2, 3, 4 *Sections:* 15301, 15302, 15303, 15304

REASONS WHY PROJECT IS EXEMPT: Project consists of minor alteration of existing public facilities involving no expansion of use beyond current levels; reconstruction of existing structures and facilities where the new structure will be located on the same site as the structure replaced and will have substantially the same purpose and capacity; construction and installation of a limited number of new small facilities; minor alterations in the condition of land that does not involve removal of healthy, mature scenic trees; included as: "modification of existing facilities for handicap access," "installation of park facilities such as interpretive panels, signs, and fencing," and "trail construction and realignment," on the Department of Parks and Recreation's list of exempt activities, in accordance with CCR § 15300.4.

CONTACT: Heidi West

Northern Service Center



PHONE NO.: (916) 445-8783

EMAIL: ceqansc@parks.ca.gov

Christina M. Aceituno

1/8/09

Date

Accessibility Section Manager