



State of California – The Resources Agency
DEPARTMENT OF PARKS AND RECREATION
NOTICE OF EXEMPTION

TO: Office of Planning and Research
1400 Tenth Street
Sacramento, CA 95814
FAX (916) 323-3018

FROM: Department of Parks and Recreation
Northern Service Center
One Capitol Mall, Suite 400
Sacramento, CA 95814

PROJECT TITLE: Campground Accessibility Improvements

LOCATION: Indian Grinding Rock State Historic Park

COUNTY: Amador

DESCRIPTION OF THE NATURE AND PURPOSE OF PROJECT: Upgrade existing facilities at Indian Grinding Rock State Historic Park to comply with the Americans with Disabilities Act (ADA) and meet requirements in the "California State Parks Accessibility Guidelines." Work will:

Campsite 7

- Remove asphalt from an approximately 1900 square foot campsite area.
Import 6 cubic yards of aggregate/soil mix and pour asphalt/concrete to level the 900sqft parking area.
Build an approximately 36" tall retaining wall around the 40' by 22' camping area, import 50 cubic yards of aggregate to level and top with native soil and aggregate mix.
Grind to ground level the existing 24" wide by 12" high tree stump.
Place 4' by 6' wooden boards along both sides of the path from the campsite to the restroom approximately 4' wide and 80' long, fill area between the boards with aggregate, and top with native soil and aggregate mix to level.
Excavate up to 12" deep by 3" wide to set a new fire ring, 24" deep, 6" wide for the barbeque pedestal, and place picnic table.

Campsite 13

- Excavate up to 24" deep and 6" wide to install a barbeque pedestal and place picnic table with anchor.
Excavate 8 holes up to 24" deep and 8" wide to reset 8 parking bollards.
Remove 1300sqft of asphalt from parking area and approach then pour new asphalt/concrete pad.
Add soil and aggregate to level a 600 sq ft area from the parking area to the campsite.
Excavate up to 30" diameter to install a dry sump drainage and install new water station.
Add another rail to the 40' long split rail fence to increase the height of the fence.
Build an approximately 48' long by 1" tall retaining wall, import 20 cubic yards of aggregate to level a 20" by 20" area for the campsite, in the new aggregate location pour concrete to make a 6" deep and 8' slab, install faucet and dry sump well (drain) to replace water station.

Campground Shower Building

- Replace 700sqft of asphalt with asphalt/concrete; work area includes the parking area, curbs, and side walk.

PUBLIC AGENCY APPROVING THE PROJECT: California Department of Parks and Recreation


NAME OF DIVISION OR DISTRICT CARRYING OUT THE PROJECT: Acquisition and Development

EXEMPT STATUS: [X] Categorical Exemption Classes: 1, 3, 4 Sections: 15301, 15303, 15304

REASONS WHY PROJECT IS EXEMPT: Project consists of the minor alteration of existing public structures and facilities involving negligible expansion of use beyond current levels included as "modification of existing facilities for handicap access" in the Department of Parks and Recreation's list of exempt activities in accordance with CCR § 15300.4, the construction and location of limited numbers of new small facilities and the minor alteration in the condition of land that does not involve removal of healthy, mature, scenic trees.

CONTACT: Stephanie Coleman
Northern Service Center

PHONE NO.: (916) 445-8779
EMAIL: scoleman@parks.ca.gov



Signature of Jennifer Harris
Date: 5-26-11
Accessability Section